

SSO PROGRAM STATUS – SEPTEMBER 2012

Program Highlights

- 108 Active Projects
 - 31 Projects Completed (\$199.5M Construction Value)
 - 40 pump stations have been upgraded or replaced
 - 7,096 manholes have been inspected, rehabilitated or replaced
 - 202,899 linear feet of force main improvements
 - 1,563,150 linear feet of gravity main improvements
 - Since 2008, SSOs have been reduced by 70%
 - 41 Projects Under Construction (\$622M Construction Value)
 - 36 Projects In Design (\$335M Construction Value)
- 354 Different Program Partners

Projects Scheduled to Advertise for Construction Bids

The following projects are expected to advertise for construction bids during **October 2012**. As projects are advertised for construction bid, they will be posted on the SSO Program Calendar at www.brprojects.com.

Government Street – South Acadian Capacity Improvement Project (09-GS-MS-0043): Located primarily in the mid-city area of Baton Rouge, this project consists of approximately 11,000 linear feet (LF) of gravity sanitary sewer pipeline replacement with diameters ranging from 12 to 27 inches. Expected to advertise in October 2012.

Plank Road – Kleinpeter Road Capacity Improvement Project (09-GS-UF-0028): Located in the North Baton Rouge area, the purpose of this project is to upsize approximately 12,500 linear feet of gravity sewer pipeline, ranging from 12 to 42 inches in diameter, as well as approximately 12,000 linear feet (LF) of forcemain pipeline ranging from 8 to 30 inches in diameter. Expected to advertise in October 2012.

Airline Highway – Goodwood Blvd Phase 2 Rehabilitation Project (11-AR-MS-0028): The purpose of this project is to rehabilitate the sewer collection system in the south-central portion of East Baton Rouge Parish. This project will include the inspection of 280,525 linear feet of sewer pipe, ranging from 6 to 26 inches in diameter. Additionally, 3,750 active laterals and 1,226 manholes will be inspected and rehabilitated where needed. Expected to advertise in October 2012.

South Boulevard – St. Joseph Street, Phase B Capacity Improvement Project (07-PS-BD-048A): This project consists of new forcemain of approximately 1,400 linear feet, ranging from 24 to 30 inches in diameter along River Road. It also includes approximately 2,500 linear feet of new 36 inches in diameter of gravity sewer pipe along South Blvd. Expected to advertise in October 2012.

Jones Creek Road – Tiger Bend Road Rehabilitation Project: This project involves rehabilitating the sewer collection system located in the south-east portion of East Baton Rouge Parish and is included in the South Gravity Hydraulic Basin. Approximately 247,500 linear feet (lf) of sanitary sewer pipe will be inspected and rehabilitated where necessary. Addition, 3,564 active laterals and 1,122 manholes will be inspected and rehabilitated where needed. Expected to advertise in October 2012.