

# SSO PROGRAM STATUS – SEPTEMBER 2013

## Program Highlights

- 109 active projects
  - 49 projects completed (nearly \$500M construction value)
  - 23 projects under construction (over \$340M construction value)
  - 37 projects in design (over \$270M construction value)
- Over 375 Program partners

## Looking Ahead

The following projects are expected to advertise for construction bids during **3<sup>rd</sup> quarter 2013**. As projects are advertised for construction bid, they will be posted on the SSO Program calendar at [www.brprojects.com](http://www.brprojects.com).

**Government St - S Acadian Thwy Sewer Area Upgrades (09-GS-MS-0043):** This project will upgrade about 9,800 LF of gravity main ranging from 12 to 27 in. in diameter near Government St between Foster St and Acadian Thwy.

**South Blvd - St Joseph St - Phase B (08-GS-ST-018B AND 09-GS-UF-008B):** This project consists of approximately 1,400 LF of new gravity sewer ranging from 10-12 in. diameter along River Road and about 2,500 LF of new 36 in. diameter gravity sewer pipe along South Blvd.

**Scenic Hwy - Spanish Town Rd Area Rehabilitation Project (Phase 1) (12-AR-MS-0039):** Located north of I-10 and south of Hollywood St, this rehab project will consist of repairing defects in the system.

**O'Neal Ln Pump Stations Improvements (Group A) (10-PS-MS-0050):** This project will upgrade 17 pump stations so that they are capable of handling peak flow ranging between 122 gpm to 21,930 gpm to work in conjunction with force main upgrades in the southern portion of the parish.