



## SSO PROGRAM STATUS – APRIL 2014

### Program Highlights

- 110 active projects
  - 49 projects completed (over \$500 M construction value)
  - 32 projects under construction (over \$475 M construction value)
  - 29 projects in design (over \$275 M construction value)
- Over 430 Program partners

### Looking Ahead

The following projects are expected to advertise for construction bids during the coming months. As projects are advertised for construction bids, they will be posted on the SSO Program calendar at [www.brprojects.com](http://www.brprojects.com).

**Multiple Pump Stations – Burbank Dr – Siegen Ln (11-PS-MS-0026):** This project involves replacing 6 pump stations able to handle peak wet weather flows ranging between 170 and 10,140 gpm.

**Highland Rd Sewer Area Upgrades (Group A) (11-FM-MS-004A):** This project will upgrade or replace 12,320 LF of gravity main ranging between 12 and 42 in. in diameter and 11,410 LF of force main ranging between 6 and 24 in. in diameter.

**Highland Rd Sewer Area Upgrades (Group B) (11-FM-MS-004B):** This project will upgrade or replace 18,380 LF of gravity main ranging between 8 and 42 in. in diameter and 4,940 LF of force main ranging between 8 and 10 in. in diameter.

**South Basin Coordination (TBD):** Located in the southern portion on the parish, this project will connect projects in the south basin.

**Plank Rd – Port Hudson Rd Sewer Area Upgrades (11-FM-MS-0036):** This project will upgrade or replace 24,630 LF of gravity main ranging between 6 and 14 in. in diameter.

**East Blvd - Government St Area Rehabilitation Project (12-AR-MS-0041):** This rehab project, located along the bank downtown and extending out past 22<sup>nd</sup> St, will consist of correcting defects in the system.

**Scenic Highway – Spanish Town Rd Area Rehabilitation Project (Phase 2) (13-AR-MS-0032):** This rehab project, located in the Capital Heights area, consists of correcting defects in the system.