



SSO PROGRAM STATUS – NOVEMBER 2015

Program Highlights

- 110 active projects
 - 68 projects completed (over \$770 M construction value)
 - 28 projects under construction (over \$315 M construction value)
 - 14 projects in design (nearly \$160 M construction value)
- Over 450 Program partners

Looking Ahead

The following projects are expected to advertise for construction bids during the coming months. For more information visit www.brprojects.com.

Sherwood Forest Blvd- Goodwood Blvd Sewer Area Upgrades (11-FM-MS-0005): This capacity project involves upsizing 13,350 LF of gravity main ranging between 8” and 36” in. in diameter and constructing 15,780 LF of force main ranging between 8 and 18 in. in diameter.

Oak Villa Blvd- Monterrey Blvd Sewer Area Upgrades (11-FM-MS-0025): This project involves constructing approximately 1,050 LF of gravity main ranging between 8” and 36” in diameter and constructing approximately 15,000 LF of force main ranging between 8” and 14” in. in diameter.

Multiple Pump Stations: Highway 61 – Plank Road (11-PS-MS-0035): This pump station project involves upgrading or replacing 5 pump stations with peak wet weather pumping capacity between 320 GPM and 9,000 GPM.

Florida Blvd Pump Stations Improvements Project (11-PS-MS-0003): This pump station project involves upgrading or replacing 8 pump stations with peak wet weather pumping capacity between 530 GPM and 21,240 GPM.