



## SSO PROGRAM STATUS – JANUARY 2015

### Program Highlights

- 110 active projects
  - 58 projects completed (over \$595 M construction value)
  - 30 projects under construction (over \$435 M construction value)
  - 22 projects in design (over \$230 M construction value)
- Over 450 Program partners

### Looking Ahead

The following projects are expected to advertise for construction bids during the coming months. For more information visit [www.brprojects.com](http://www.brprojects.com).

**South WWTP Landscape Buffer Area Project (13-TP-MS-0046):** This project consists of creating a landscape buffer around a portion of the South WWTP.

**Airline Hwy Pipeline Project Group A (10-GS-MS-007A):** This capacity project involves upsizing 4,520 LF of gravity main ranging between 8 and 24 in. in diameter and constructing 23,450 LF of force main ranging between 36 and 48 in. in diameter.

**Sherwood Forest Blvd- Goodwood Blvd Sewer Area Upgrades (11-FM-MS-0005):** This capacity project involves upsizing 14,760 LF of gravity main ranging between 8 and 36 in. in diameter and constructing 15,780 LF of force main ranging between 8 and 18 in. in diameter.

**Zachary Area Transmission Network Improvements Project Phase 5 (06-WC-IF-014E):** The project will replace a pump station and improve piping. The new pump station will be able to hand a peak wet weather flow of 3,380 gpm.

**Ardenwood Dr - Winbourne Dr Area Rehabilitation Project (13-AR-MS-0034):** This rehabilitation project consists of correcting defects in the system.